

JUL 03 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1996 NOV 22 AM 11: 07

Patricia A. Monley
REGISTER OF DEEDS

For corners in
Marquette

(County)

Located in:

Corner Code #

1. Public Land Survey

T 51N R 28W

D13

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

LIBER **R1** PAGE **320**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Oct 02 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

(D13) South Quarter corner of Section 32. Corner established in 1845 by Austin Burt: "40.00 Set qr. Section post. Birch 16 N60E 45, B. Ash 16 N55W 39". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D13) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on the Fifth Correction Line at the proportionate North Latitude between recovered Standard Corners 2618.86' east and 7987.53' west, being proportionate to the original record. At the position for the corner, I placed a 1"IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussme
DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D13) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following new bearing trees:

- 18" Y. Birch S47W 11.5' "1/4S NBT"
- 9" Y. Birch N48E 19.7' "1/4S NBT"
- 6" Sugar S59E 26.9' "1/4S NBT"
- 16" Hemlock S12E 23.0' "1/4S NBT"

The pipe is driven into the roots of a 14" Maple N45W 1.2 ft. distant. The top center of the cap marks the corner position. Bearings are magnetic.

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a BH blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11-5-96

For the Michigan Department of Natural Resources - Forest Management Division