

REC

JUL 03 2000

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 NOV 22 AM 11: 07

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Marquette

(County)

Located In:

Corner Code #

1. Public Land Survey

T 51N R 28W E13

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Patricia A. Manley REGISTER OF DEEDS

LIBER R1 PAGE 321 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

Oct 02 1995

I, Stephan J. Szyszkoski, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

(E13) Standard corner common to Sections 32-33. Corner established in 1845 by Austin Burt; "West on south side of Sec. 33...67.50 Stream 5 L wide C NNE...80.00 Set post corner of Secs. 32&33. Hemlock 18 N30E 32, Hemlock 10 N65W 17". Found no subsequent record.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Larry J. Busceme DATE 10/28/96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E13) Original post not recovered. Recovered a 1 1/2" x 48" long iron pipe at record bearing and distance from a decaying hemlock stump, possibly one of the original bearing trees. The stump is of record size, with markings no longer visible. No trace of the 2nd original bearing tree was found. The pipe was found 8.5' westerly from the proportionate position between standard corners 1.5 miles east and 2 miles west, and 2.3' south of a latitudinal line between them. Distance east to a dry stream bed checks very well with the record. The pipe has been witnessed long ago with a blazed "X" and a notch on a 14" Sugar (noted below) and a cedar signature tree, now dead and down. Accepted the monument as the best available evidence of the position of the original corner. Left the pipe in place and drove into it a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E13) Set 1" pipe with 4" MDNR cap in a 1 1/2" found iron pipe. Blazed and scribed the following new bearing trees: 14" Sugar S35E 5.0' "S1 NBT" 10" Cedar S03E 29.0'(slope) "S1 NBT" 17" Hemlock S47W 34.0' "S1 NBT" 12" Sugar N52E 19.3' "S33 NBT" Bearings are magnetic. Distances horizontal unless noted.

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by Stephan J. Szyszkoski Surveyor's Michigan License No. 33986

Date 11-5-96

For the Michigan Department of Natural Resources - Forest Management Division