

JUL 03 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 NOV 22 AM 11:07

Patricia A. Monley REGISTER OF DEEDS

For corners in

Marquette

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 28W G13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER R1 PAGE 323 Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Sep 26 1995

I, Stephan J. Szyszkoski, in a field survey on, 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G13) Corner common to Sections 33-34. Corner established in 1845 by Austin Burt: "West on South Side Section 34...40.00 Set cr. section post...47.30 Stream 8 C NE, 51.17 Hemlock 20 in dia., 72.80 Hemlock 25 in dia, 80.00 Set Post Corner of Sections 33-34 Maple 7 N17E 14, B.Oak 5 N23W 22". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G13) Original post and accessories not recovered. Line trees noted above not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on the Fifth Correction Line at the proportionate North Latitude between monumented corners at E13 and H13, and 40.00 chains, proportionate to the original record, west of H13. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner, the 1/4 corner on the north side of Section 6, T50N-R28W is 81.77' west, along the Correction Line.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Signature: Gary J. Buosone DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G13) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:

- 14" Sugar S62E 6.0' S6 NBT
10" Sugar S56W 16.8' S6 NBT
7" Sugar N69W 9.4' S33 NBT
8" Hemlock N30E 33.7' S34 NBT
Bearings are magnetic.

MDNR monuments are 1"IDx32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

New bearing trees are marked with a 3H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.



Signed by Stephan J. Szyszkoski Surveyor's Michigan License No. 33986

Date 11-5-96