

JUL 03 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 NOV 22 AM 11:07

Patricia A. Mosley REGISTER OF DEEDS

For corners in Marquette

Located In: Corner Code #

Table with 3 columns: Description (Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.), Located In (T, S), and Corner Code # (51N, 28W, H13).

LIBER R1 PAGE 324 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Sep 06 1995

I, Stephan J. Szyszkoski, in a field survey on 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

(H13) South 1/4 corner Section 34. Corner remonumented in 1950 by Dean C. DeLaMater, RLS: "Both original BT's still visible, and in excellent condition. One, a large maple, is still alive. Set 1" pipe with 4" brass cap. 14" S. Maple NSW 26 links, 12" Y. Birch N55E 31 links". Original 1845 record by Austin Burt shows Sugar 12 N26E 54 for a bearing tree.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H13) Found and accepted a 1" ID iron pipe with a 4" brass Michigan Dept. of Conservation cap, in good condition, at record bearing and distance from one original Sugar bearing tree, now a 29" Sugar, alive and standing in excellent condition, with old 8H blaze and original scribing visible. DeLaMater's two NBTs are gone. Left the monument in place and marked new witnesses as described below. The other original bearing tree was not recovered.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Larry J. Bussard DATE 10/28/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H13) Found 1" pipe with 4" brass cap. The original Sugar BT: 29" Sugar N33E 35.8' meas. to a notch in old chopping, apparently made subsequent to original marking.

MDNR monuments are 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum Michigan Department of Natural Resources tablet, stamped with Township, Range, corner ID, date of placement, and "PS 33986".

Blazed and scribed the following new bearing trees:

New bearing trees are marked with a 8H blaze and a lower blaze at the root crown. The blazes are scribed as indicated in quotation marks at left, with NBT or BT (as noted) being on the lower blaze. Distances are horizontal (unless noted) and measured from the corner to the inside of a notch cut into the bottom of the lower blaze.

- 5' Maple N86E 32.5' "1/4S NBT"
6' Maple N03W 13.1' "1/4S NBT"
7' Maple S43W 44.7' "1/4S NBT"

Bearings are magnetic.

Signed by Stephan J. Szyszkoski Surveyor's Michigan License No. 33986

Date 11-5-96



For the Michigan Department of Natural Resources - Forest Management Division