

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1999 DEC 22 AM 11:28

*Patricia A. Hanley*  
REGISTER OF DEEDS

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MARQUETTE  
(County)

Located In: Corner Code #

1. Public Land Survey T 51N R 27W G-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LIBER **R2** PAGE 232

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on April 20, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9: Section Corner common to Sections 21, 22, 27, and 28, T51N-R27W.  
1846: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:  
14" Y. Birch S72W, 22 L 6" Maple N78E, 24 L

No Date: MCRC Field Notes (No book #) Pg. 96-97, indicate the corner as an Iron Pin. No accessories given.

No Date: MCRC Field Notes (No book # given), indicate the corner as an Iron Pin. No accessories given.

(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9: 1999: No original corner evidence found. Found and accepted a 1 1/4" inside diameter iron pipe broke off and flush with the ground. Bearings and distances to found references checked well with those recorded in L. 4, RC Pg. 254.  
Distance North is 2621.52', East is 2649.89'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9: 1999: Replaced 1 1/4" pipe and set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.1' above ground. Measured found references:  
7" W. Birch N38W, 17.95' (E.C.I. - NBT-1983) 8" Triple Maple East, 21.36' (E.C.I. - NBT-1983)  
9" Maple S47E, 29.27' (E.C.I. - NBT-1983)

Established new references:  
6" Hemlock S60W, 32.63'

Green Steel Sign Post w/ Yellow Survey Marker Sign South, 1.49'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
T51N-R27W Corner Search Report 99100

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Kerry J. Bussme*  
DATE 10/11/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589

**G-9: SECTION**  
**PART A CONTINUED:**

No Date: MCRC F.B. #674, pp. 14-15, indicates the corner as an Iron Pipe referenced by:

8" Poplar	S42W,	32.5'	4" Poplar	N19W,	27.0'
5" Poplar	N53E,	45.7'	4" Poplar	S87E,	46.6'

No Date: The Marquette County Road Commission (MCRC) Government Corner Index Book for Section 21, indicates the corner as an Iron Pipe referenced by:

8" Poplar	S42W,	32.5'	4" Poplar	N19W,	27.0'
5" Poplar	N53E,	45.7'	4" Poplar	S87E,	46.6'

1983: An LCRC recorded by Charles F. Clark, P.S. #25836 in L. 4, RC Pg. 254, indicates the corner as a found 2" Iron Pipe referenced by 16d nails in:

6" W. Birch	N45W,	18.07'	8" Maple	East,	21.30'
12" Poplar	S65W,	12.22'	8" Maple	S50E,	29.22' (Nail/Collar in tree)

No Date: A survey sketch by Engineering Consultants, Inc., indicates a found 2" iron pipe at the SW corner of Section 22. Referenced by:

6" W. Birch	N45W,	18.07'	8" Maple	East,	21.30'
12" Poplar	S65W,	12.22'			