

SURVEY & REMONUMENTATION

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

DEC 12 PM 2:29

Patricia L. Manley
 REGISTER OF DEEDS

For corners in

<u>Marquette</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>51N</u> R <u>29W</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **R2** PAGE **243**
 Register of Deeds Stamp & File Number

I, Gerald W. Carlson, in a field survey on June 21, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9: Southeast Corner of Section 24: 1845: Austin Burt's original township line survey notes described the corner as a post referenced by:

6" Sugar, S 13 W, 20 L 8" Sugar, N 71 W, 17 L

1846: William Ives's original subdivision notes for T51N-R29W added the following two references:

12" Y. Birch, S 79 E, 34 L 12" Sugar, N 69 E, 55 L

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

RATIFIED BY PEER GROUP
P.A. 345 OF 1980

Harry F. Bussard
 DATE 11/6/00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9: 2000: Found remnants of a wood post on the ground in the area identified by a 22" Hemlock with a Ford location tag and a 1/2" pipe painted blue. There was also blue painted lines in four cardinal directions from this location. After an extensive search the location of where the wood post stood in the ground could not be determined. I located corners 1/2 mile East and West and 1 mile North and South from this location with GPS. The corners North, East and South were original BT corners. The corner 1/2 mile West was an Norm Thompson (RLS 4348) corner circa 1946. Thompson does not indicate any measurements of these four lines. The 2 mile measurement North and South is long by 4.14 feet making each mile 5282.07 compared to 5280 (GLO) which I used for the North-South location. The 1/2 mile measurement from the South 1/4 Corner of Section 24 to the straight line proportion location for the Southeast Corner of Section 24 between the corners 1 mile North and South is long by approximately 1 chain (55.84'). Assuming this 1/2 mile is 1 chain longer than GLO, the distance between the corners 1/2 mile East and West is 5514.44' compared to 5512.32'(GLO + 1 chain). I used this assumption to fix the East - West location of this corner. The distance 1/2 mile West is 2712.98 (67.04' longer than recorded GLO and 1.04' longer than recorded GLO + 1 chain). The 1/2 mile distance East is 2801.46' compared to 2800.38' (GLO). This position is 11.02' East of the straight line proportion location between the BT corners 1 mile North and South. No evidence was found at locations 1/2 mile North and South. This location falls on the North-South blue paint line and 10' +/- South of the East-West blue paint line and lines up with the old Ford location tag and old healed blaze on a 22" Hemlock. The only Norm Thompson information found was that the 6" Sugar, S 13 W was marked "OK 25" and the 12" Sugar N 69 E was listed as "OK". No Thompson NBT information was found in the notes. No original GLO evidence was found on the ground.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2000: Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by 20d double head nails in:

- 22" Hemlock N 17 W 29.76' w/old Ford location tag and healed over blaze
- 5" Maple N 53 E 26.64'
- 11" Y. Birch S 35 E 19.95'
- 18" Maple S 55 W 33.84'
- 6' green steel fence post with sign, North, 2.0'; monument projects 0.45'
- Generic location tag N 09 E, 14.8'; 1/2" pipe painted blue, N 42 E, 13.5'
- Bearing trees have painted face, butt and side nail blazes and engraved B.T. tags affixed



Signed by Gerald W. Carlson Date 8-21-00

Surveyor's Michigan License No. 24589