

1993

COARSE

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On 12/29, 1992
Chairman

For corners in MENOMINEE (County) Located In: Corner Code #
1. Public Land Survey T 32N R 27W A-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Stamp: REGISTERED FOR RECORD 93 DEC 29 PM 3:33
PAGE # 25 OF 4 BARBARA MORRIS REGISTER OF DEEDS MENOMINEE, MI 49855
Register of Deeds Stamp & File Number

I, WILLIAM LENCA, in a field survey on October 21 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: ORIGINAL B.T.'s: Black Ash, 16", N46°W, 36 lks Black Ash, 16", S35°W, 84 lks

Original Survey by James H. Mullett in 1848. All evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" diameter Iron Rod and cap set by George B. Wilson, RLS 17607, in the centerline of a North - South County Road, and in line with an old fence line running West from this location. This corner has been used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen A1NBF30 Aluminum Monument stamped for corner location:

- 6" dia. White Ash N32°E 52.97 feet
9" dia. White Ash S22°E 46.80 feet
5" dia. White Birch S30°W 50.78 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked WITNESS MARKER N85°W - 28.60 feet (At Survey Sign Post)

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.

Signed by William Lenca Date December 27, 1993
Surveyor's Michigan License No. 26461