

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County Land Survey Remanumentation Peer Group Under Act 345 Of P.A. Of 1990 On 12/29 1993
Chairman

For corners in MENOMINEE (County) Located In: Corner Code #
1. Public Land Survey T 32N R 27W A-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

RECEIVED FOR RECORD
93 DEC 29 PM 3:49
PAGE # 3 OF 4
BARBARA MORRIS
REGISTER OF DEEDS
MENOMINEE MI 499
Register of Deeds Stamp & File Number

I, WILLIAM LENCA, in a field survey on NOVEMBER 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: ORIGINAL B.T.'s: W. Pine, 30", N43°W, 28 lks; Y. Pine, 22", S42°W, 38 lks; Hemlock, 8", N16°E, 21 lks; Hemlock, 8", S52°E, 11 lks

Original Survey by James H. Mullett in 1848.

PERPETUATION: LCRC No. 93, Book 1 by George B. Wilson, RLS No. 17607, in March, 1975.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" dia. Aluminum pipe/3" dia. cap set by George B. Wilson as stated in LCRC No. 93, mentioned in "A" above. Mr. Wilson found evidence of 3 original B.T.'s and a mark in the soil at the location of the original post. This corner falls on an old fence running East - West and 66.6 feet East of an old fence corner, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Existing 2" diameter Aluminum Pipe/3" dia. cap stamped for corner:

Table listing monument details: 5" dia. Oak N45°E 35.85 feet; 10" dia. Cedar S70°E 44.31 feet; 7" dia. White Ash S60°W 66.05 feet; 5" dia. White Ash N42°W 63.17 feet; Metal Survey Sign Post - South 1.1 feet



Signed by William Lenca Date December 15, 1993
Surveyor's Michigan License No. 26461