

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Michigan County  
Land Survey Reestablishing  
Four Group Under Act 345 of

P.A. of 1990 to 12/28 1993

For corners in  
MENOMINEE  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 27W  
T 33N R 27W

B-1 ✓  
B-13 33/27

2. Property Controlling  
in Section

S T R  
S T R

3. Miscellaneous  
Property in Sec.

S T R  
S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, WILLIAM LENCA, in a field survey on July 21 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s: Tamarack, 18", N30°E, 14 lks  
Cedar, 6", N45°W 10 lks

Original Survey by James H. Mullett in 1848.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I had set a 1/2 inch diameter Iron Rod, 18 inches long in a August, 1981 survey. The Iron has been destroyed, but the corner position was re-established from 4 bearing trees which I had marked in 1981. The corner was set in line with the centerline of a county road and lane running East from this position. The East-West position for this corner was established by doubling the distance from the Northeast Corner (C-1) and the East 1/16 fence. This position checked with a GLO Terrain call to a well defined 14 foot high ridge 264 feet West. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen Drivable F-130 Aluminum Monument stamped for corner:

6" dia. Spruce	N48°E	17.17 feet
5" dia. Tamarack	S20°E	24.30 feet
6" dia. Cedar	S50°W	25.08 feet
6" dia. White Birch	N43°W	11.33 feet
Metal Survey Sign Post	North	0.75 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape.  
All distances to trees are measured to nails in side of tree.

Signed by William Lenca

Date December 27, 1993

Surveyor's Michigan License No. 26461

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

RECEIVED FOR RECORD  
DEC 29 PM 3:55  
PAGE # 40, 128 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		6	5	4	3	2	1						
2													
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

