

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/28 1993

Alce J. Smith
Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------|-------------|-------|
| 1. Public Land Survey | | T 32N R 27W | B-3 |
| | | T _____ | _____ |
| | | T _____ | _____ |
| | | T _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | _____ |
| | S _____ | T _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | _____ |
| | S _____ | T _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD
93 DEC 29 PM 3:55
PAGE # 17 1344
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49859
Register of Deeds Stamp & File Number

I, WILLIAM LENCA, in a field survey on October 20 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5			4			3		2		1
3		7				8			9		10		11
4													12
5													
6		18				17			16		15		14
7													13
8		19				20			21		22		23
9													
10		30				29			28		27		26
11													
12		31				32			33		34		35
13													36

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL B.T.'s: Hemlock, 12", N66.5°E, 26 lks
Birch, 18", S32°W, 18 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2 inch diameter iron rod 18 inches long which I set in a survey dated August, 1981. The corner was placed in line with old fences running North and South from this location, and 33 feet North of an old East-West fence. This position fits with the centerline of an old lane to the West, the centerline of a county road to the East, and fits with the 1/16 fence to the East. This location is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set A1NBF30 Berntsen Monument stamped for corner:

4" dia. White Pine	N53°E	56.14 feet
8" dia. White Pine	S23°E	34.27 feet
6" dia. Tamarack	S86°W	82.37 feet
7" dia. White Ash	N42°W	148.80 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.

Signed by William Lenca Date December 27, 1993
Surveyor's Michigan License No. 26461

