

1893

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On 12/28 1993

COMMISSION

For corners in

MENOMINEE (County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 27W B-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

RECEIVED FOR RECORD DEC 29 PM 3:49 BARBARA MORRISON REGISTER OF DEEDS MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

I, WILLIAM LENCA, in a field survey on Oct. 21 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: ORIGINAL B.T.'s: Hemlock, 10", S48°W, 17 lks Beech, 14", N13°W, 33 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

PERPETUATION: George B. Wilson, RLS No. 17607, in Plat of Survey dated Apr. 17, 1971; Plat of Survey dated Nov. 1971; Certified Survey No. 17; Certified Survey No. 135. William Lenca, RLS No. 26461, in Certified Survey No. 349; Certified Survey No. 361 dated Aug. 2, 1983.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" diameter Iron Rod beneath Railroad Spike in the surface of an asphalt county road. The corner position falls in the centerline of county roads North - South and West. This corner has been used by local surveyors over the past 20 years, as noted in "A" above, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner:

Set 5/8" x 24" Iron Rod/2" dia. Aluminum cap marked WITNESS MARKER as follows: S42°E 127.05 feet (near 12" dia. W. Pine) N55°E 50.15 feet (near Metal Survey Sign Post) S55°W 64.02 feet (near 6" dia. Maple) N55°W 46.24 feet (near 12" dia. Norway Pine)

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.

Signed by William Lenca Date December 28, 1993 Surveyor's Michigan License No. 26461

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

