

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/28 199 93
Mc Davis
Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 32N R 27W C-5
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD
93 DEC 29 PM 3:53
PAGE # 26 Bl. 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, William Lenca, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s: Spruce, 8", S35°W, 22 lks
Cedar, 10", N35°E, 14 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

PERPETUATION: Albert Haas, County Surveyor, in a 1900 survey indicates this corner is a "4" inch Cedar Post in center of road identified from former surveys". This survey is on record in "County Surveyors Record" Book on page 16 of the Menominee County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
George B. Wilson in Certified Survey No. 204 shows a Subdivision of Section 8, T32N-R27W indicating the location of corner C-5

Found a broken Berntsen Monument (W1B) in the centerline of a County Road running North and South from this location. A county road runs West from this location and the position falls in line with old occupation to the East. This location fits well with information contained in Albert Haas' 1900 survey, and also matches George B. Wilson's position for this corner. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 24" Iron Rod/3/4" dia. Alum. cap stamped for corner in Monument Box:
- 5" dia. White Ash N45°E, 106.10 feet
- 5/8" x 24" Iron Rod/2" Alum. cap (WITNES MARKER) S40°E, 50.05 feet
- " " " " " S38°W, 68.76 feet
- " " " " " N31°W, 61.92 feet

NOTE: All bearings are magnetic bearings; distances are measured with steel tape. distances to trees are measured to nail in side of tree.

Signed by William Lenca Date December 13, 1993
Surveyor's Michigan License No. 26461