

**SURVEY & REMONUMENTATION**

APR 11 1995

For corners in MENOMINEE  
(County)

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1980 On DEC 16 1994  
M. MORRISON RLS  
ACTING Chairman

RECEIVED FOR RECORD  
94 DEC 27 AM 10:49  
PAGE # 204 BK 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49858  
Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T <u>32NR</u> <u>27W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

William Lenca Apr. 17 1994

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - W. Pine, 12", S44°W, 08 lks; Cedar, 8", S65°E, 11 lks. No original evidence for this corner was recovered.
- 1968: Plat of Survey by Robert Olsen, surveyor, describes this corner as "Ex. Iron". The measurement to the Section Corner 1/2 mile to the East is shown as 2748.8 feet. No ties are given.
- 1981: Certified Survey No. 270 by George B. Wilson, RLS No. 17607, shows this corner in a subdivision of Section 29, T32N-R27W. The corner monument is not described.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1" diameter iron pipe 48" long at an ancient fence corner. Fences run North and East from this location. The measured distance from this corner to the Section Corner 1/2 mile East is 2749.16 feet compared to Robert Olsen's measurement for this 1/2 mile of 2748.8 feet. This corner has been accepted and used by local surveyors for at least 26 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 60" Alum. Rod/3-1/4" dia. Alum. Cap stamped for corner in place of 1" dia. Iron Pipe:

10" dia. White Pine	N29°E	65.30 feet	Scr. NBT
12" dia. White Ash	S34°E	4.61 feet	Scr. NBT
8" dia. White Ash	S60°W	17.38 feet	Scr. NBT
6" dia. White Pine	N19°W	15.08 feet	Scr. NBT
Carsonite Marker Post	West	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 07, 1994

Surveyor's Michigan License No. 26461