

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/23 1993
Mr. Powell
Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>32N</u>	R <u>27W</u>	<u>E-1</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

RECEIVED FOR RECORD
93 DEC 29 PM 3:55
PAGE # 43 136 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49859

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

1. William Lenca, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s:

- Sugar, 13", N46°E, 67 lks
- Sugar, 20", N56°W, 80 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

Corner was perpetuated in May of 1893 by A.L. Hillis.

George B. Wilson perpetuated Hillis' corner in April of 1974, LCRC 108, Book 1.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" dia. Iron Pin set by George B. Wilson. Wilson States that he set this bar over the top of a 1 1/2" square iron bar established by A.L. Hillis in May of 1893. This corner has been used for control in many surveys for several years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3 1/2" dia. Alum. cap stamped for corner in Monument Box:

5/8" x 24" Iron Rod/2" Alum. cap (WITNESS MARKER)	N05°E	31.45 feet
" " " " " "	N53°E	51.12 feet
Northwest Corner of House Foundation	S15°E	149.78 feet
8" dia. Willow	S10°W	31.15 feet

NOTE: All bearings are magnetic bearings; distances are measured with steel tape. distances to trees are measured to nail in side of tree.

Signed by William Lenca Date December 2, 1993
Surveyor's Michigan License No. 26461