

Dee Davis  
Chairman

1993

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

	Located In:	Corner Code #
1. Public Land Survey	T 32N R 27W	E-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD  
93 DEC 29 PM 3:53  
PAGE # 16 Bl. 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL B.T.'s:
- Beech, 10", N42°E, 33 lks
  - Beech, 10", N22°W 35 lks

Original Survey by James H. Mullett in 1848. No evidence of Original B.T.'S found. This corner was perpetuated by George B. Wilson as indicated in Certified Surveys No. 358 (rec. in 1983) and No. 461 (rec. in 1986).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" dia. Aluminum Rod/3 1/4" dia. Aluminum cap at old fence corner. Fences run North, West, East and South from this location. This corner has been used for several surveys in the area, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" dia. Aluminum Rod/3 1/4" dia. Aluminum cap stamped for corner:
- |  |       |            |
|--|-------|------------|
| 12" dia. White Ash                               | N29°E | 32.20 feet |
| 10" dia. Twin W. Ash                             | N78°E | 23.93 feet |
| 5/8" x 24" Iron Rod/2" Alum cap (WITNESS MARKER) | S05°W | 5.80 feet  |
| 14" dia. White Ash                               | N62°W | 6.60 feet  |
| Survey Sign Post                                 | North | 1.0 feet   |

NOTE: All bearings are magnetic bearings; distances are measured with steel tape. distances to trees are measured to nail in side of tree.

Signed by William Lenca Date December 2, 1993  
Surveyor's Michigan License No. 26461