

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/23, 199 93
Met Davis
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>27W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
93 DEC 29 PM 3:54
PAGE # 28 124
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s: Beech, 18", N17°W, 16 lks
Birch, 12", S28°E, 12 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

PERPETUATION: Albert Haas, County Surveyor, in a 1900 survey states "4 inch Cedar Post on West side of road identified from former surveys". This survey is on record in "County Surveyors Record" Book on page 16, Menominee County Records. LCRC No. 207, Book 1, recorded by George B. Wilson, RLS 17607, in Dec. 1979. Certified Survey No. 204 by George B. Wilson shows subd. of Sec. 8, 32/27, indicating the location of corner D-5.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a broken Berntsen Monument (W1B) set by George B. Wilson as indicated in LCRC 207 and in Certified Survey No. 204 as referenced above. This corner falls in the centerline of County Road No. 577, in line with the centerline of Elmwood Road running East from this location and in line with an old fence line running West from this location. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3/4" dia. Aluminum cap stamped for corner in Monument Box:		
5/8" x 24" Iron Rod/2" dia. Alum cap (WITNESS MARKER)	N48°E	55.87 feet
" " " " " "	S50°E	61.58 feet
" " " " " "	S48°W	37.55 feet
" " " " " "	N50°W	62.75 feet
Metal Survey Sign Post	S50°E	62 feet

NOTE: All bearings are magnetic bearings; distances are measured with steel tape.

Signed by William Lenca Date December 13, 1993
Surveyor's Michigan License No. 26461