

SURVEY & REMONUMENTATION COMMISSION
APR 1 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Remonumentation
 Fee Group Under Act 306 Of
 P.A. Of 1990 On DEC 16 1994
Mr. David RLS
 Chairman

For corners in MENOMINEE (County)
 Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>32NR</u>	<u>27W</u>	<u>E-11</u>
	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
2. Property Controlling in Section	S	_____	_____	_____
	S	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	_____	_____
	S	_____	_____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECEIVED FOR RECORD
 94 DEC 27 AM 10:48
 PAGE # 197 BK. 9
 BARBARA MORRIS
 REGISTER OF DEEDS
 MENOMINEE, MI 49983
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca in a field survey on Apr. 07 1994
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1847: Original Survey by James H. Mullett - B.T.'s - Tamarack, 8", S41°W, 11 lks; Tamarack, 6", N49°E, 18 lks. No original evidence for this corner was recovered.
 - 1958: Survey by Robert Olsen, surveyor - Notes state that "stake for corner in hole of fence corner post for fence West & North."
 - 1973: L.C.R.C. No. 68 by George B. Wilson, RLS No. 17607, states - "Found stake set by Mr. Robert Olsen in airport survey - The stake falls at a very old fence corner." Wilson set a 2" x 30" iron pipe/brass cap - no ties.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- We found a 2 inch diameter iron pipe with brass cap at the corner of a very old fence running West and North from this location. The corner monument is about 3 inches under water and falls near the East edge of a gas pipeline in a marshy area. There is a large amount of occupation in the area which matches the corner as monumented. This corner has been accepted and used by local surveyors for more than 35 years, and is accepted as the best available evidence of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 2" x 30" Galvanized Iron Pipe/2" dia. Brass Cap stamped for corner:

Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	N03°W	61.05 feet
Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	S40°W	85.05 feet
Northeast Corner House Foundation	S75°W	143.70 feet
Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	N80°W	60.05 feet
Carsonite Marker Post	South	0.1 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 12, 1994
 Surveyor's Michigan License No. 26461