

SURVEY & REMONUMENTATION
APR 11 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of

P.A. Of 1990 On Dec 16 1994

For corners in
MENOMINEE
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	32N	R	27W	E-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

ACTING REGISTRAR
 RECEIVED FOR RECORD
 DEC 27 AM 10:48
 #196
 ARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca May 05 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - Fur, 8", S10°W, 20 lks; Aspen, 12", S73°E, 23 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1886: Survey by Orson Burlingame showing partial subdivision of Section 33, T32N-R27W. The corner monument is described as a bolt.
- 1972: Certified Survey No. 9 by George B. Wilson, RLS No. 17607, shows the corner as it relates to other corners in the SW1/4 of Section 33, T32N-R27W. The corner monument is described as an iron pin.
- 1982: L.C.R.C. No. 376 by George B. Wilson, RLS No. 17607, states - "Found iron pipe in road used in old surveys. A W-1-B Monument was set. Ties - Deep-1 magnets - NE - 36.76' & SE - 18.34'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a cast aluminum W-1-B Berntsen Monument. The cap had been sheared off by a snow plow, but the base was still in proper location. The monument falls in the centerline of an East - West County Road and in line with an old fence running South, and fits well with Wilson's measurements shown in Certified Survey No. 9. This location has been used and accepted as the corner location for many years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner in Monument Box:

SW Corner of House foundation	N30°E	78.95 feet
NW Corner of House foundation	S25°E	72.20 feet
NE Corner of House foundation	S40°W	123.02 feet
Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	N28°W	92.14 feet
Carsonite Marker Post	N28°W	92.14 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 12, 1994
 Surveyor's Michigan License No. 26461