

SURVEY & REMONUMENTATION

JUN 23 1994

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 5118, 1994

McDaw
Chairman

For corners in
COMMISSION
MENOMINEE
(County)

	Located In:	Corner Code #	
1. Public Land Survey	T <u>32N</u> R <u>27W</u>	<u>E-13</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECEIVED FOR RECORD

94 MAY 20 PM 3:32

PAGE #75 BK. 4

BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on Nov. 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847 - Original Survey by James H. Mullett - B.T.'s - Jack Pine, 22", N56°E, 171 lks ; Jack Pine, 20", N65°W, 3.45 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1886 - Plat of Survey by Orson Burlingame, Surveyor, shows a section subdivision of Section 33, T32N-R27W. The corner monument is not described and no witnesses are given.
- 1972 - Certified Survey No. 9 recorded by George B. Wilson, RLS No. 17607, states that a concrete monument was found at this location. The record measurements in this survey along the South Line of the SW 1/4 of Section 33 compare very closely to Burlingame's measurement.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1-1/2" diameter iron rod in a concrete monument on the centerline of 18th avenue extended west. Burlingame's measurement east from this corner is 2656. The present measurement east from this corner to a very old fence running north at the position of the S1/4 corner of Section 33 is 2654.3. The monument is therefore accepted as a careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted existing 1-1/2" diameter Iron Rod in concrete monument:

5/8" x 24" Iron Rod/2" Alum. cap marked Witness Marker	N62°E	36.26 feet
5/8" x 24" Iron Rod/2" Alum. cap marked Witness Marker	S34°E	40.84 feet
5/8" x 24" Iron Rod/2" Alum. cap marked Witness Marker	S37°W	38.27 feet
5/8" x 24" Iron Rod/2" Alum. cap marked Witness Marker	N50°W	46.21 feet
Metal Survey Sign Post	South	29.7 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by *William Lenca* Date April 27, 1994
Surveyor's Michigan License No. 26461