

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/29 199 93
Mr. Davis
Chairman

RECEIVED FOR RECORD
93 DEC 29 PM 3:52
PAGE # 14
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in

MENOMINEE
(County)

Located In:

Corner Code --#

- 1. Public Land Survey T 32N R 27W F-1 (F-13-33/27)
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, William Lenca, in a field survey on September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL B.T.'s:

- Cedar, 12", N23°E, 21 lks
- Tamarack, 14", N60°W, 6 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

PERPETUATION: William Lenca in 1987, recorded in LCRC Book 3, page 751

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 24" Iron Pin/Ident. cap set on line and midway between the Northeast Corner and the Northwest Corner of Section 4, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3/4" dia. Alum. cap stamped for corner in Monument Box:

- | | | | |
|--|-------|------------|--|
| 7" dia. White Ash | N18°E | 31.28 feet | |
| 5" dia. Ironwood | S41°W | 65.30 feet | |
| 5" dia. White Ash | N72°W | 51.31 feet | |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap (WITNESS MARKER) | S06°W | 29.82 feet | |
| Survey Sign Post | S06°W | 30.0 feet | |

NOTE: All bearings are magnetic bearings; distances are measured with steel tape. distances to trees are measured to nail in side of tree.

Signed by William Lenca Date December 2, 1993
Surveyor's Michigan License No. 26461

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

