

REMARKS

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 12/28, 199 93

Chairman  
RECEIVED FOR RECORD  
93 DEC 29 PM 3:54  
PAGE # 29  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>27W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s: Tamarack, 8", N27°E, 09 lks  
Tamarack, 8", S74°W, 04 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

PERPETUATION: Certified Survey No. 269 by George B. Wilson (RLS No. 17607) shows the location of this corner as it relates to other corners in section 16.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Berntsen W1C 30" long monument/4" diameter aluminum cap (sheared off by snowplow). This corner was found in the location indicated by information contained in Certified Survey No. 269. This corner is also shown in an unrecorded survey map dated 1/12/74 by George B. Wilson, indicating that the corner position was established in the centerline of an East - West county road and placed 2.2 chains (Original Field Notes) from a swamp edge. This position has been used in several surveys over the past 20 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3/4" dia. Alum. cap stamped for corner in Monument Box:

7" dia. Tamarack	N60°E	76.55 feet
5" dia. Cedar	S42°E	69.83 feet
7" dia. Tamarack	S60°W	70.60 feet
7" dia. Tamarack	N02°W	50.37 feet
Metal Survey Sign Post	S08°W	33.0 feet



NOTE: All bearings are magnetic bearings; distances are measured with steel tape. distances to trees are measured to nail in side of tree.

Signed by William Lenca Date December 13, 1993

Surveyor's Michigan License No. 26461