

SURVEY & REMONUMENTATION
APR 11 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>32N</u>	R	<u>27W</u>	<u>F-11</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

William Lenca May 05 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - White Ash, 10", N08°E, 8 lks; Birch, 12", S44°W, 13 lks. No original evidence for this corner was recovered.
- 1980: Certified Survey No. 188 by George B. Wilson, RLS No. 17607, shows this corner in relation to other corners in the NW 1/4 of Section 33, T32N-R27W. The corner monument is not described.
- 1980: Certified Survey No. 189 by George B. Wilson, RLS No. 17607, shows a subdivision of Section 28, T32N-R27W. The survey shows this corner as being at a single proportionate position. The corner monument is not described.
- 1984: Airport Boundary Survey by FOTH & VAN DYKE, Consulting Engineers, indicates that a 1" Iron Pipe was found. The corner is shown in relation to other Airport Boundary Corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1 inch diameter iron pipe in a location which matches distances to the Section Corners East and West of this location, as shown in Certified Survey No. 188 and Certified Survey No. 189. The location also fits with Airport Boundary corners established in the 1984 Airport Survey noted above. This corner has been used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2-1/2" x 30" Alum. Pipe/3-1/4" dia. Alum. cap stamped for corner (in place of Existing Iron Pipe):

Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	N35°E	16.08 feet
6" dia. Aspen	N90°W	9.15 feet
Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	S88°E	3.43 feet
Set 5/8" x 24" Iron Rod/2" dia. cap marked WITNESS MARKER	S33°W	7.65 feet
Survey Sign Post	N70°E	1.0 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Dec. 12, 1994

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. of 1988 On DEC 16 1994
W. Lenca RLS
 ACTING Chairman

RECEIVED FOR RECORD
 94 DEC 27 AM 10:48
 PAGE # 194 Bk. 4
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE MI 49803
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

