

SURVEY & REMONUMENTATION

APR 11 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of

P.A. of 1988 On DEC 16, 1994

W. Davis RLS
ACTING Chairman

For corners in:
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>32NR</u>	<u>27W</u>	<u>G-08</u>
	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
2. Property Controlling in Section	S	_____	_____	_____
	S	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	_____	_____
	S	_____	_____	_____

RECEIVED FOR RECORD
94 DEC 27 AM 10:45
PAGE # 193 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William Lenca Nov. 29 / 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - Tamarack, 12", N13°E, 8 lks; Cedar, 10", S56°W, 19 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1976: Certified Survey No. 63 by George B. Wilson, RLS No. 17607, shows this corner in relation to lot corners in the survey, and in relation to other GLO Corners. The corner monument is not described.
- 1982: Certified Survey No. 319 by William Lenca, RLS No. 26461, describes the corner in the map legend as "Found Magnet".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. Nail set over the top of a "Deep-1 Magnet" in the South Lane of an East - West County Road and in line with an old fence line running South from this location. The position of the magnet fits with alignment and distance to lot corners shown in Certified Survey No. 63. This corner position has been used by local surveyors for at least 18 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner in Monument Box (in place of Existing Magnet):

8" dia. Cedar	N35°E	38.87 feet	Scr. NBT
8" dia. Cedar	S61°E	77.76 feet	Scr. NBT
5" dia. White Ash	S50°W	31.06 feet	Scr. NBT
5" dia. Cedar	N47°W	64.98 feet	Scr. NBT
Survey Sign Post	S00°W	21.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca

Date Dec. 15, 1994

Surveyor's Michigan License No. 26461