

**SURVEY & REMONUMENTATION COMMISSION**  
**APR 1 1 1995**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of

P.A. of 1990 On DEC 12 1994

For corners in  
**MENOMINEE**  
 (County)

Located In: Corner Code #

1. Public Land Survey	T	<u>32NR</u>	<u>27W</u>	<u>G-09</u>
	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
2. Property Controlling in Section	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____
	S	_____	T	_____

*Mc Davis BLS*  
**REGISTER OF DEEDS**  
 # 192 BK 4  
 DEC 27 AM 10:48  
 RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**William Lenca** Apr. 08 1994

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1847: Original Survey by James H. Mullett - B.T.'s - Maple, 12", N32°W, 50 lks; Maple, 12", N62°E, 15 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1977: Certified Survey No. 100 by George B. Wilson, RLS No. 17607, shows a subdivision of Sections 27 & 34, T32N-R27W. The corner monument for corner G-9 is not described.
- 1982: L.C.R.C. No. 375 by George B. Wilson, RLS No. 17607, states "Found pin at fence corner North and East - Set HDR Monument - TIES: Deep - 1 - SW 64.00 feet; Deep - 1 - SE - 50.00 feet."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We found a 3/4" dia. aluminum rod 5' long with a 3-1/4 inch diameter aluminum cap (Berntsen HDR Monument) 50 feet North of the centerline of 48th Avenue, at an old fence corner as described in L.C.R.C. No. 375. Fences run North and East from this location. The corner position fits with distances to other Section Corners as shown in Certified Survey No. 100. This corner position has been used by local surveyors for at least 17 years, and is accepted as the best available evidence of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Accepted 3/4" dia. alum. rod 5' long/3-1/4" dia. alum. cap stamped for corner:

7" dia. White Ash	N48°E	60.50 feet	Scr. NBT
5/8" x 24" Iron Rod/2" alum. cap marked WITNESS MARKER	S25°W	118.87 feet	@ NE Cor Stone Barn
Nail in Power Pole	S28°W	2.08 feet	
5" dia. White Ash	N22°W	56.35 feet	Scr. NBT
Carsonite Marker	East	2.0 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca

Date Dec. 15, 1994

Surveyor's Michigan License No. 26461