

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Re-enumeration
 Fee Group Under Act 346 Of

P.A. Of 1988 On DEC 16 1994
M. L. DAVIS RLS
 ACTING

SURVEY & RE-ENUMERATION
 APR 11 1995
COMMISSION

For corners of _____ Located In: _____ Corner Code # _____

1. Public Land Survey T 32NR 27W _____ G-12
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD
 94 DEC 27 AM 10:4
 PAGE # 190 BK 9
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49853
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca Nov. 22 1994
 I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1847: Original Survey by James H. Mullett - B.T.'s - Tamarack, 10", N14°E, 06 lks; Tamarack, 10", N17°W, 17 lks. All original evidence for this corner has been destroyed by Airport Construction.
 1977: Certified Survey No. 100 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Sections 27 and 34, T32N - R27W. The corner monument is not described.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 In 1984-1984 Airport reconstruction destroyed this corner location. In our 1994 re-enumeration survey, we recovered the Center Quarter Corner and the Southwest Corner of Section 34. We had previously re-established the Northwest Corner of Section 34. Based on measurements shown in Certified Survey No. 100, we established a proportional position from 3 directions for the corner. The position fit very closely with Wilson's bearings and distances shown on Certified Survey No. 100. We accepted this location as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2-1/2" x 30" Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner:
 Survey Sign Post N00°W 0.5 feet
 Nothing else nearby for ties



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape.

Signed by William Lenca Date Dec. 15, 1994
 Surveyor's Michigan License No. 26461