

**SURVEY & REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1980 On DEC 16 1994

For corners in APR 1 1 1995

MENOMINEE  
(County)

**COMMISSION**

Located In:

Corner Code #

- |                                    |   |              |            |             |
|------------------------------------|---|--------------|------------|-------------|
| 1. Public Land Survey              | T | <u>32N</u> R | <u>27W</u> | <u>H-09</u> |
|                                    | T | _____R       | _____      | _____       |
|                                    | T | _____R       | _____      | _____       |
|                                    | T | _____R       | _____      | _____       |
| 2. Property Controlling in Section | S | _____T       | _____R     | _____       |
|                                    | S | _____T       | _____R     | _____       |
| 3. Miscellaneous Property in Sec.  | S | _____T       | _____R     | _____       |
|                                    | S | _____T       | _____R     | _____       |

M. Davis BLS  
ACTING Chairman  
PAGE # 189  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858  
RECEIVED FOR RECORD  
DEC 27 AM 10:48

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Lenca, in a field survey on May 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - Tamarack, 12", S57°E, 23 lks; Tamarack, 12", N65°W, 17 lks. All original evidence for this corner has been destroyed by Airport Construction.
- 1955: Northernnaire Subdivision No. 1 by Robert D. Washburn, RLS No. 6844, shows a tie to this corner. The monument is described as a T-Iron.
- 1977: Certified Survey No. 100 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Sections 27 and 34, T32N - R27W. The corner monument is not described.
- 1980: Certified Survey No. 194 by George B. Wilson, RLS No. 17607, shows this corner as it relates to corners shown in Northernnaire Subdivision No. 1. The corner monument is described as a concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a concrete monument in a Monument Box in the center of 48th Avenue (newly constructed in 1984-1985 Airport Construction Project. The position of this monument matches measurements to corners shown in Certified Survey No. 100 and also matches measurements to corners shown in Certified Survey No. 194. Wilson's measurement from this corner to an iron pipe at the E1/16 Corner on the North Line of Section 27, as shown in Northernnaire Subdivision No. 1, matches with Washburn's measurement to this same iron pipe. It therefore appears that the concrete monument is in the same position as the T-Iron described by Washburn in the above mentioned plat. This corner has been used in a great number of surveys by local surveyors, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3-1/4" dia. Alum. cap stamped for corner on existing concrete monument in Monument Box:

5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	N06°W	49.70 feet	
5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	S67°E	120.38 feet	@ 7" Birch
5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	S42°W	69.70 feet	@ Ch. Lk. Fc. Cor.
5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	N48°W	114.01 feet	@ 4" Maple
Survey Sign Post	N06°W	50.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape.

Signed by William Lenca Date Dec. 15, 1994

Surveyor's Michigan License No. 26461

Dec. 15, 1994

