

# SURVEY & REMONUMENTATION

APR 11 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Fee Group Under Act 346 of  
P.A. of 1989 On DEC 16 1994  
*W. Lenca RLS*  
*ACTING*

For corners in COMMISSION  
MENOMINEE  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>32N</u> R <u>27W</u>	Corner Code # <u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
 DEC 27 AM 10:48  
 # 183 BK 4  
 BARBARA NORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49853

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Lenca, in a field survey on May 05, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1847: Original Survey by James H. Mullett - B.T.'s - Aspen, 8", S29°E, 17 lks; Y. Pine, 18", N10°W, 30 lks. All original evidence for this corner has been destroyed by Highway Construction.
- 1977: Certified Survey No. 100 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 27 and 34, T32N-R27W. The corner monument is not described.
- 1988: L.C.R.C. No. 850 by Neil E. Hill, RLS No. 27447, states that 1953 Highway plans show 3" pipe in Mon. Box, 2.47' E. of c/l - Witnesses gone. 1984 MDOT research - found Axle Shaft in Mon. Box 2.47' E. of c/l - TIES: N45°E - 40.91' - Top center Fire hydrant; S80°E - 36.45' - P.P.; S20°W - 70.84' - Light Pole; S85°W - 29.28' - E. Rim Water Valve Box. Hill found Axle shaft in Mon. Box - agrees with 1984 witnesses and is locally accepted. He uses 1984 ties.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We found an axle shaft in a Monument Box 2.47 feet East of the centerline of U.S. Highway 41 in location which agrees with the witnesses described in L.C.R.C. No. 850. This location also fits with Wilson's measurements to corners 1/2 mile North and 1/2 mile West, as shown in Certified Survey No. 100. This corner has been used for at least 40 years by local surveyors, and is accepted as the best available evidence of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Accepted Axle Shaft in Monument Box:**

NW Corner of Bank Building	S59°W	120.85 feet	
5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	N43°W	35.22 feet	@ back of curb
5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	S46°W	104.22 feet	
5/8" x 24" Iron Rod/2" Alum. cap marked WITNESS MARKER	N72°E	126.55 feet	@ SW Cor. Bldg

**NOTE: All bearings are magnetic bearings. All distances are measured with EDM.**

Signed by William Lenca Date Dec. 15, 1994

Surveyor's Michigan License No. 26461