

1993

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of

P.A. of 1990 On 12/23, 1993

For corners in MENOMINEE (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 32N R 27W K-6

2. Property Controlling in Section S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Chairman Barbara Morrison

DEC 29 PM 3:49

REGISTER OF DEEDS MENOMINEE, MI 49859

RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, WILLIAM LENCA, in a field survey on October 29 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 ORIGINAL B.T.'s: Cedar, 10", N64°W, 05 lks
 Spruce, 15", N67°E, 23 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by county road improvements.

PERPETUATION: William Lenca, RLS 26461, in July, 1981 - recorded in LCRC No. 324, Book 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 30 inch long plastic Berntsen Monument with a 4 inch diameter Aluminum cap. The cap had been sheared off by a county snowplow. This corner was established by retracement of Robert Olsen's survey dated Oct. 22, 1957. The corner position falls in the centerline of an East-West County Road and in line with an old fence running South from this location, and has been used by local surveyors over the past 35 years. This location is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner in Monument Box:

Set 5/8" x 24" Iron Rod/2" dia. Aluminum cap marked WITNESS MARKER as follows:

- S35°E 42.74 feet (1' from 12" Maple)
- S35°W 60.26 feet (1' from 7" W. Ash)
- N37°W 72.50 feet (1' from 4" W. Ash)
- N12°E 31.28 feet (At Metal Survey Sign Post)

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.

Signed by William Lenca Date December 27, 1993
 Surveyor's Michigan License No. 26461

| | A | B | C | D | E | F | G | H | I | J | K | L | I |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

