

REMONUMENTATION

1993

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of PA. Of 1990 On 12/28 1993

COMMISSION

For corners in MENOMINEE (County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 27W K-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, WILLIAM LENCA, in a field survey on Sept. 17 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s: Birch, 15", N32°E, 21 lks
Hemlock, 10", S28°W, 18 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by Highway improvements.

PERPETUATION: George B. Wilson in Certified Survey No. 80 dated March, 1977 shows he established a 4" square concrete monument at this corner. This monument was destroyed by Highway improvements, and was replaced in August, 1985 by myself and George B. Wilson with a 30 inch long plastic Berntsen monument with a 4 inch diameter Aluminum cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 30 inch long plastic Berntsen Monument mentioned in "A" above, with the cap sheared off by a snowplow. This corner position falls in the centerline of an East-West County Road and in a position that matches closely with an old survey by Kieth Roberts, dated November 10, 1953, and with old M-35 Highway plats. This corner position has been used by local surveyors over the past 40 years and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3 1/4" dia. Alum. cap stamped for corner in Monument Box:

- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER S85°E 101.70 feet
6" dia. White Ash S33°E 152.75 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER S48°W 76.98 feet
S.E. Corner of House N53°W 86.22 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.

Signed by William Lenca Date December 20, 1993

Surveyor's Michigan License No. 26461

RECEIVED FOR RECORD
93 DEC 29 PM 3:22
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49855
Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

