

# SURVEY & REMONUMENTATION

JUN 23 1994

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 5/18 1994  
McDermott  
Chairman

For corners in  
MENOMINEE  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>28W</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
94 MAY 20 PM 3:31  
PAGE # 60 BK. 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Lenca, in a field survey on March 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

ORIGINAL B.T.'s: Y. Pine 20", N85°W, 80 lks  
W. Pine, 20", S19°E, 112 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by County Road improvements.

PERPETUATION: 5/7/1975 - LCRC No. 96A recorded by George B. Wilson, RLS No. 17607, contains testimony of Mr. Emil Dvorchek, resident since 1914, that the existing fence along the section line was built in about 1896 by N. Ludington Company. Mr. Wilson states he set a 2" dia. alum. pipe with alum. cap stamped. NBT's - 7" Oak - 224 deg azm - 45.0'; 5" Oak - 180 deg azm - 53.2'; 1" Oak - 148 deg azm - 55.0'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found a 2" dia. Aluminum Pipe with cap stamped as described in LCRC No. 96A. This corner falls in the centerline of a County Road East-West and in line with an old fence line running North from this location. According to the residents statement in LCRC No. 96A, this fence is approximately 100 years old. Accepted this corner as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Accepted existing 2" dia. Alum. Pipe / 2-1/2" dia. Alum. cap stamped for corner:

1/2" dia. Iron Rod	Scr. NBT	N03E	32.97 feet
8" dia. Oak	Scr. NBT	S50E	52.54 feet
6" dia. Oak	Scr. NBT	S54W	43.75 feet
9" dia. Oak	Scr. NBT	N69W	69.05 feet
Metal Survey Sign Post		North	33.0 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date April 16, 1994  
Surveyor's Michigan License No. 26461

