

# SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. of 1990 Cg 10/31 199 7

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

McDowell RLS  
Chairman

### SECTION

MENOMINEE  
(County)

Located In:	Corner Code #
T <u>32N</u> R <u>28W</u>	<u>K-3</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

REGISTER FOR RECORD  
 97 NOV 21 PM 3:19  
 PAGE # 535, BK 5  
 REGISTERED LAND SURVEYOR  
 WILLIAM LENCA  
 LICENSE NO. 26461

Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Mar. 06, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

#### A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 12" - N30°W - 32 lks.; Cedar, 12" - S28°E - 32 lks. No evidence of the original corner or its accessories were found.
- 1993: CERTIFIED SURVEY No. 796 recorded by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in the area.

#### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a 1993 survey of Section 12, T32N-R28W, we made a search for this corner and found the remains of an old squared wood post in a location that fits reasonably well with measurements to other corners in the area. We re-monumented the position with a 1" x 30" aluminum pipe with a 3-1/4" diameter aluminum cap stamped for the corner location. We also established 4 B.T.'s as described in part C below. In 1997 we found this corner and the 4 B.T.'s in good condition, and accepted the existing monument as the best available evidence of the position of the original corner.

#### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 1" x 30" alum. pipe/3-1/4" alum. cap stamped for corner:

12" dia. Tamarack	N19°E	23.11 feet	Scr. NBT
12" dia. Tamarack	S70°E	98.53 feet	Scr. NBT
9" dia. Tamarack	S18°W	63.83 feet	Scr. NBT
5" dia. Maple	S86°W	18.52 feet	Scr. NBT
Carsonite Marker	S32°W	3.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Apr. 08, 1997

