

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/31, 1997
McGraw RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T <u>32</u> N R <u>28</u> W	<u>L-5</u>
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

REGISTERED LAND SURVEYOR
97 MAR 21 PM 3:19
540 BKS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Mar. 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Becch, 6" - S62°W - 15 lks.; Hemlock, 10" - N07°E - 14 lks. No evidence of the original corner or its accessories were found.
- 1982: L.C.R.C. No. 369 recorded by George B. Wilson, RLS No. 17607, states "Old fence corner, no other evidence. Set HDR 1 Monument at corner. Witness: Deep I, 1 foot North & 1 foot West.
- 1982: CERTIFIED SURVEY No. 295 recorded by, George B. Wilson, RLS No. 17607 shows this corner as it relates to other corners in Section 13, T32N-R28W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 3/4" diameter aluminum rod with a 3-1/2" diameter aluminum cap marked "MENOMINEE COUNTY SURVEY CORNER" in a location matching record distances to other corners in Section 13, T32N-R28W, as shown in Certified Survey No. 295. This corner fits well with existing lines of occupation, has been accepted by local surveyors for at least 15 years; and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" alum. rod/3-1/4" alum. cap stamped for corner:

6" dia. White Ash	S73°E	11.14 feet	Scr. NBT
30" dia. White Ash	S20°W	16.19 feet	Scr. NBT
20" dia. White Ash	N70°W	21.30 feet	Scr. NBT
12" dia. White Ash	N20°W	16.31 feet	Scr. NBT
Metal Survey Sign Post	N50°W	2.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Apr. 10, 1997

540