

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 12/23 19993  
Alfred Lewis  
 Chairman

For corners in <u>MENOMINEE</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 32N R 27W T <u>32N</u> R <u>28W</u> T _____ R _____ T _____ R _____	A-4 <u>M-4</u> ✓
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
 93 DEC 29 PM 3:55  
 PAGE # 22  
 BARBARA MORRISO  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49858  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

~~AKA T32N R28W M-4~~

I, WILLIAM LENCA, in a field survey on October 21 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 ORIGINAL B.T.'s: Cedar, 10", N60°W, 04 lks  
 Cedar, 10", S55°W, 14 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by County Road improvements.

PERPETUATION: William Lenca, RLS No. 26461 - LCRC No. 721, Book 3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3/4" diameter Iron Rod 5 feet long with 3-1/4" diameter cap marked for corner. This monument was set by William Lenca, RLS 26461, in a survey dated April, 1986. The corner was placed in line with an old fence running East from this location and in line with the centerline of a county road running South. This location is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 3/4" dia. Alum. Rod/3-1/4" dia. Alum. cap stamped for corner:

6" dia. White Ash	N67°E	23.90 feet
8" dia. White Ash	S46°W	42.70 feet
7" dia. White Ash	N85°W	45.77 feet
7" dia. White Ash	N07°E	23.88 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. All distances to trees are measured to nails in side of tree.



Signed by William Lenca Date December 27, 1993  
 Surveyor's Michigan License No. 26461