

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee

County

Located In:

Corner Code: //

1. Public Land Survey	T 33N R 26W	E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 8 T 33N R 26W	9
	S 8 T 33N R 26W	7
3. Miscellaneous Property in Sec.	S 8 T 33N R 26W	6
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	8	7	6	5	4	3	2	1					
7													
8	9	8	7	6	5	4	3	2	1				
9													
10	10	9	8	7	6	5	4	3	2	1			
11													
12	11	10	9	8	7	6	5	4	3	2	1		
13													

I, Gerald L. Wiggins, in a field survey on 4-25 & 8-21 & 8-22, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4 Quarter Corner common to sections 8 and 9. OBT'S: Tamarack 8", S35°W, 06 lks. & Tamarack 8", S75°E, 11 lks.

9 East 1/16 Corner of Section 8. Not previously set.
 7 North 1/16 Corner common to Sections 8 and 9. Not previously set.
 6 Northeast 1/16 Corner of Section 8. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Corner set at found point of original stake, one original Tamarack stump bears S35°W, 3.96' top and bottom scribe marks very visible and a Tamarack stump bottom bears S75°E, 7.26' no scribe marks visible.
 9 Corner set M.P.O.L. between East 1/4 Corner and computed Center Corner of Section 8 by closed traverse.
 7 Corner set M.P.O.L. between Northeast Corner and East 1/4 Corner of Section 8.
 6 Corner set at center of N.E. 1/4 of Section 8 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monument set at all four corners.

E-4 8" Cedar, N20°E, 25.8' 9 5" B. Spruce, S86°E, 26.6' 7 6" W. Birch, N68°E, 8.1'
 6" Tamarack, East, 21.65' 3" W. Birch, S41°E, 19.7' 6" Cedar, S66°W, 13.3'
 6" Tamarack, S19°W, 21.3' 5" B. Ash, S18°W, 14.15' 8" Cedar, N41°W, 23.8'
 5" Tamarack, N60°W, 5.8' 5" B. Spruce, N47°W, 34.1' 10" Twin Cedar, S27°E, 16.1'

6 8" Cedar, N28°E, 35.5' & 6" Cedar, East, 33.5' & 9" Cedar, S1°W, 14.95" & 5" Cedar, N79°W, 5.1'

Signed by

Gerald L. Wiggins
 Gerald L. Wiggins

Date 9-4-90

Surveyor's Michigan License No.

23521

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 20, 1971
 No. 23521
 REVISED MAY 14, 1975
 REVISED JAN. 1983

