

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**Menominee**  
(County)

Located In:

Corner Code *≠*

1	Public Land Survey	T	33N	R	26W	F-3
		T	33N	R	26W	F-4
		T		R		
		T		R		
2	Property Controlling in Section	S	9	T	33N R 26W	8
		S	9	T	33N R 26W	15
3	Miscellaneous Property in Sec.	S		T		
		S		T		

Register of Deeds Stamp & File Number

4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **Gerald L. Wiggins**, in a field survey on **6-6 & 8-13**, 19 **90**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-3 Quarter Corner common to Sections 4 and 9. **OBTS: Tamarack 30, N63°E, 10 lks & Tamarack 20, S78°E, 10 lks.**

F-4 Center Quarter Corner of Section 9. **Not previously set.**

8 West 1/16 Corner of Section 9. **Not previously set.**

15 West 1/16 Corner common to sections 9 and 16. **Not previously set.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

F-3 Corner set M.P.O.L. between northeast and northwest corners of section 9. Distance west to swamp edge fits original notes.

F-4 Corner set at intersection of N-S 1/4 line and E-W 1/4 line of section 9 by closed traverse.

8 Corner set M.P.O.L. between west 1/4 corner and center corner of section 9.

15 Corner set M.P.O.L. between southwest corner and south 1/4 corner of section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.  
**DNR MONUMENT SET AT ALL FOUR CORNERS.**

F-3 6" Cedar, N63°E, 31.15' & 14" Cedar, S39°E, 21.65' & 12" Spruce, S65°W, 24.1' & 4" Cedar, N12°W, 19.9'

F-4 6" Cedar, N27°E, 21.45' & 6" Cedar, S43°E, 8.65' & 6" Cedar, S73°W, 15.6' & 6" Cedar, N46°W, 31.85'

8 13" Cedar, N34°E, 35.6' & 4" Cedar, S37°E, 12.05' & 14" Cedar, S56°W, 31.95' & 15" Cedar, N41°W, 12.6'

15 8" Hemlock, S85°E, 9.9' & 6" Y. Birch, S38°E, 33.0' & 8" Hemlock, S44°W, 33.9' & 8" Hemlock, N42°W, 27.85'

Signed by Gerald L. Wiggins Date 9-4-90  
 Surveyor's Michigan License No. 23521

