

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee	Located In:	Corner Code #/
(County)		
1. Public Land Survey	T 33N R 26W	E-3
	T 33N R 26W	D-3
	T . . . R . . .	_____
	T . . . R . . .	_____
2. Property Controlling in Section	S . . . T . . . R . . .	_____
	S . . . T . . . R . . .	_____
3. Miscellaneous Property in Sec.	S . . . T . . . R . . .	_____
	S . . . T . . . R . . .	_____

Register of Deeds Stamp & File Number

4. Lot No, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald L. Wiggins, in a field survey on 8-16- 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3 Northeast corner of Section 8. Set by Frank Bray in 1965. 5" Cedar, N50°E, 18.0'
 6" Cedar, N43°W, 14.35'

D-3 Quarter Corner common to Sections 5 and 8.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3 Corner re-witnessed as set by Frank Bray R.L.S. in 1965 from original B.T.'S.

D-3 Corner set at a found 1/2" Iron at intersection of Fence Line South and County Roads North and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


DNR Monument set at both corners.

E-3 Bray's two Cedars are still green and standing. Marked a 5" Tamarack, S60°E, 18.2' and 4" Tamarack, S66°W, 18.7'.

D-3 6" Cedar, N58°E, 20.05' & 5" Cedar, S58°E, 25.3' & 7" Cedar, S7°W, 20.45' & 5" Cedar, S61°E, 47.85'

Signed by Gerald L. Wiggins
 Gerald L. Wiggins
 Surveyor's Michigan License No. 23521

Date 9-4-90



FORM APPROVED BY STATE BOARD OF LAND SURVEYORS, JAN. 28, 1975
 23521
 REVISED MAY 14, 1975
 REVISED JAN., 1983