

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

McLain RLS
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T33N R 27W

M-6

T R

T33N R 26W

A-6 ✓

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

RECEIVED FOR RECORD
95 DEC 27 PM 3:29
PAGE # 274 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
HERE AT THE COUNTY CLERK'S OFFICE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

(SAME AS CORNER A06 T33N-R26W)

I, William Lenca, in a field survey on Aug. 04, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 16" - S65°W - 14 lks; Hemlock, 24" - N54°W - 5 lks. All original evidence has been destroyed by county road improvements.

1984: L.C.R.C. No. 596, recorded by George B. Wilson, RLS No. 17607, states that a Deep-1 magnet was set in place of a found iron pin in Road intersection. TIES: Deep-1 - SW - 43.6' (found); Pin - NW - 46.1' (found).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In our 1995 Remonumentation Survey in T33N-R27W, we recovered a "Deep - 1" magnet in the centerline of County Roads running North - South and East - West. This monument fits with existing lines of occupation, has been used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

8" dia. White Pine	N68°E	104.72 feet	Scr. NBT
6" dia. Tamarack	S52°E	79.49 feet	Scr. NBT
13" dia. White Ash	S61°W	67.52 feet	Scr. NBT
9" dia White Ash	N43°W	65.85 feet	Scr. NBT
Metal Survey Sign Post	S42°E	55.3 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 27, 1995

274