

SURVEY & REMONUMENTATION

OCT 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
PA. Of 1990 On 10/11 1999
McDermis RLS
Chairman

For corners in
MENOMINEE

(County)

Located In:	Corner Code #
T <u>33N</u> R <u>26W</u>	B-5
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Aug., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REGISTERED FOR RECORD
99 OCT 15 PM 1:40
PAGE # 01 BK 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49856
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Birch, 10" - N10°E - 13 lks.; Hemlock, 6" - S51°E - 24 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1901: Survey by Albert Hass, Co. Surveyor, shows this corner as it relates to other corners in Section 18. Survey states "Set 4" Cedar post in center of road in proportionate distance between section corners.
- 1987: L.C.R.C. No. 771 by William Lenca, RLS No. 26461 - Set 1/2" x 18" Iron in c/I E-W Co. Rd & in line with ancient fences N & S. This position fits well with a 1901 survey recorded in "RECORD OF SURVEYS" Book on file in Register of Deeds Office. TIES: W. Birch, 9" - N13°W - 21.55'; Red Pine, 4" - N28°E - 45.44'; W. Birch, 8" - S46°E - 38.49'; PP - S71°W - 44.75' (gone).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered the 1/2 inch x 18 inch iron set in our 1987 survey, along with the Ties as described in L.C.R.C. 771 (see part "A"). This corner falls in the centerline of an east - west county road (gravel surface) and in line with ancient fences running North and South from this location. Although this location does not exactly fit a proportional position, the fences running North and South from this location are approximately 80 to 90 years old, and appear to have been constructed based on the 1901 survey. We therefore accepted the corner location, as fenced, as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

7" dia. Norway Pine (Ex. B.T.)	N28°E	45.44 feet	Scr. NBT
9" dia. White Birch (Ex. B.T.)	S46°E	38.49 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S65°W	44.02 feet	1' N. of Power Pole
10" dia. White Birch (Ex. B.T.)	N13°W	21.55 feet	Scr. NBT
Metal Survey Sign Post			

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 31, 1999

