

# SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. Of 1990 On 12/22, 2000  
Ma. Davis RLS  
Chairman

For corners in

MENOMINEE

(County)

Located in:

Corner Code #

- |                                    |  |             |
|------------------------------------|--|-------------|
| 1. Public Land Survey              | T <u>33</u> N R <u>26</u> W            | <u>B-11</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |

Bk. 6 Pg. 204

RECEIVED FOR RECORD  
28 DEC 2000 2:31:31 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Dec., 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 12" - S65°W - 11 lks.; Cedar, 4" - N42°W - 12 lks. All original evidence for this corner has been destroyed by foresting activities.  
1980: Certified Survey No. 178 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 31, T33N-R26W. The corner is shown at a single proportional location. No monument is described.  
1983: L.C.R.C. No. 574, Book 2 by George B. Wilson, RLS No. 17607, states that an HDR Alum. Mon., rod 5' long was set by Single Proportion. TIES: Deep-1: 2' North & 2' East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a HDR Aluminum Rod Monument with a 3-1/4 inch diameter aluminum cap at a location which was 6 feet North and 0.5 feet East of the correct corner location. Since the single proportional location, and not the monument, had been accepted and used in surveys in the area for over 20 years, we moved the existing monument to the correct location, and accepted it as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" x 5' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner:

8" dia. White Birch	N41°E	14.13 feet	Scr. NBT
7" dia. White Ash	S17°E	63.42 feet	Scr. NBT
8" dia. White Ash	S87°W	56.73 feet	Scr. NBT
5" dia. Balsam	N31°W	35.31 feet	Scr. NBT
Metal Survey Sign Post	North	1.1 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 19, 2000