

SURVEY & REMONUMENTATION

JAN 09 2001

SECTION


LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. Of 1990 On 12/22, 2000
McL. Brown RLS
Chairman

For corners in
MENOMINEE
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 33N R 26W	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Bk. 6 Pg. 209



Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on Dec., 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar 14", S69°E, 4 lks.; Cedar 14", N37°E, 19 lks. Original evidence for this corner has been destroyed by logging activities.
- 1988: L.C.R.C. No. 803, Book 3, by William Lenca, RLS No. 26461 states "Set corner by double proportionate measurement between the W 1/4 Corner of Section 20 & the SW Corner of Section 29 and between the S 1/4 Corner of Section 20 & the SW Corner of Section 19. TIES: Nail in 14" White Ash, Scr. B.T., S82°E, 23.93'; Nail in 9" White Ash, Scr. B.T., N08°W, 33.62'; Nail in 8" White Ash, Scr. B.T., S82°W, 60.47'; Nail in 6" Maple, Scr. B.T., S02°E, 58.00'; Carsonite, SW, 1.34'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 5' HDR monument and 4 B.T.'s in place per L.C.R.C. 803 (see above) at a double proportional location. This corner has been accepted and used for several years, and is accepted as a careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" x 5' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner:

W. Tree of Twin 6" dia. Maple	N11°W	40.29 feet	Scr. N.B.T.
16" dia. White Ash (Existing B.T. - Set New Nail)	S82°E	24.17 feet	Scr. N.B.T.
8" dia. Maple (Existing)	S02°E	58.00 feet	Scr. N.B.T.
10" dia. White Ash (Existing B.T. - Set New Nail)	S82°W	60.47 feet	Scr. N.B.T.
Carsonite Marker	S27°W	1.34 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 20, 2000