

SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. Of 1990 On 12/22, 2000
Me. Davis RLS
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

| | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>33</u> N R <u>26</u> W | C-11 |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |

Bk 6 Pg. 211

RECEIVED FOR RECORD
28 DEC 2000 2:31:31 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct., 1900 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L |
| 1 | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | |
| 3 | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | |
| 5 | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | |
| 7 | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | |
| 9 | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | |
| 11 | | ⊙ | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | |
| 13 | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - White Pine, 16" - S51°E - 5 lks.; Hemlock, 10" - S37°E - 23 lks. Found old Pine stump fitting O.B.T., S51°E, 5 lks.
- 1980: Certified Survey #178, Book 2, by George W. Wilson, RLS No. 17607 shows corner C-11 as it relates to other corners in Section 31. States in his legend that he set a 4" square concrete monument, 36" long, pin in center.
- 1986: Certified Survey # 459, Book 3, by William Lenca, RLS No. 26461, states in his legend "4" dia. concrete monument found." at corner position for C-11.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 4" square concrete monument in location indicated by Certified Survey #178 (see above). The monument falls on the East side of a sand road. An old White Pine stump fits well with O.B.T., S51°E, 5 lks. This corner has been accepted and used by local surveyors for at least 20 years, fits well with measurements to corners in 4 directions, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 4" square concrete monument, set 3/4" Alum. cap stamped for corner location:

| | | | |
|------------------------|-------|------------|----------|
| 6" dia. Maple | N02°E | 69.17 feet | Scr. NBT |
| 8" dia. Maple | N48°E | 39.34 feet | Scr. NBT |
| 10" dia. Hemlock | S41°E | 35.68 feet | Scr. NBT |
| 11" dia. Hemlock | S61°W | 32.85 feet | Scr. NBT |
| Metal Survey Sign Post | East | 0.80 feet | |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 20, 2000