

SURVEY & REMONUMENTATION

OCT 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/11, 1999
McLain RLS
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33</u> N R <u>26</u> W	<u>E-11</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECEIVED FOR RECORD
99 OCT 15 PM 1:40
PAGE # 03 BK 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Apr., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Elm, 16" - S77°W - 66 lks.; Cedar, 4" - N62°W - 57 lks. All original evidence for this corner has been destroyed by shore erosion.
- 1955: Plat of Survey by Robert Olsen - 1-1/2" I.P. 359.4' E. of c/I M-35. TIES: 6" Ash - S88°W - 45.9'; 3" Ash - S65°W - 17.1'; 14" Ash - N72°W - 49.01'.
- 1962: OED'S SURFSIDE BEACH SUBD. recorded by Robert Olsen, RLS 10700, shows a tie to this corner.
- 1985: L.C.R.C. No. 716 (Bk 3) by George B. Wilson, RLS No. 17607, has a sketch on the back which shows this corner as it relates to other corners in Section 28, T33N-R26W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1/2 inch x 24 inch iron rod in a location matching well with Robert Olsen's 1955 survey. We also found 2 Ash Trees (S88°W - 46.76 feet and S65°W - 17.47 feet to center) which match closely with the natural witnesses shown in Olsen's survey. The distance to the centerline of Highway M-35 is 359.27 feet compared to Olsen's record distance of 359.4 feet. The corner position also matches well with distances to corners as shown in L.C.R.C. No. 716. This corner has been accepted and used in several surveys over the past 44 years, and is accepted as the best available evidence of the position of the original corner. NOTE: the GLO Notes state "40.00 - to Green Bay and set Meander Corner which answers for qtr sec. post".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

18" dia. White Ash (Not Blazed)	N36°E	106.81 feet
12" dia. White Ash (Not Blazed)	S65°W	17.47 feet
10" dia. White Ash (Not Blazed)	N88°W	46.76 feet
NE Corner of House	N11°W	94.33 feet
Metal Survey Sign Post	South	1.25 feet



NOTE: All bearings are magnetic bearings. All distances are measured with EDM. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 31, 1999