

**SURVEY & REMONUMENTATION**  
**APR 11 1995**  
**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 OF  
 P.A. Of 1990 On 12/19 19994  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49825  
 DEC 12 AM 8:57  
 RECEIVED FOR RECORD  
 # 97 B.K. 4

For corners in  
**MENOMINEE**  
 (County)

Recorded In: \_\_\_\_\_ Corner Code **H-7**

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>33N</u> R <u>26W</u> | <u>H-7</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on June 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 14", N51°E, 17 lks & Cedar, 6", S37°W, 16 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1970: Plat of Survey by George B. Wilson, dated 2/18/70, shows this corner as being 2111.54' West of the centerline of Highway M-35. No description of the corner monument is given.
- 1977: Certified Survey No. 112 by George B. Wilson, RLS No. 17607, shows this corner as being 2111.54' West of the centerline of Highway M-35. No description of the corner monument is given.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found a 1/2 inch diameter iron rod 43 inches in length in the centerline of an East - West County Road and in line with an old fence line running North from this location. This corner fits with distances shown in surveys mentioned in part "A" above. This corner location has been used by local surveyors for over 20 years and is accepted as the best available evidence of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

16" dia. White Birch	N45°E	68.18 feet	Scr. NBT
8" dia. Cedar	S36°E	52.14 feet	Scr. NBT
10" dia. Cedar	S40°W	44.49 feet	Scr. NBT
8" dia. Cedar	N14°W	41.20 feet	Scr. NBT
Survey Sign Post	S03°E	31.0 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca Date July 09, 1994  
 Surveyor's Michigan License No. 26461