

SURVEY & REMONUMENTATION

For corners in APR 11 1995
MENOMINEE
 (County) **COMMISSION**

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 12/9 199 94
McDavis RLS
 Chairman

	Located In:	Corner Code #
1. Public Land Survey	T <u>33N</u> R <u>26W</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD
 94 DEC 12 AM 8:57
 PAGE # 98 BK 1
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49856
Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on May 06, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	13	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Tamarack, 10", S35°W, 11 lks & Cedar, 8", S67°E, 17 lks. All original evidence for this corner has been destroyed by logging activities and driveway construction.
- 1985: L.C.R.C. No. 688 recorded by George B. Wilson, RLS No. 17607, states that a HDR Aluminum monument was set in place of an old wood stake along an E - W fence line. 2 deep-1 magnets were set - 1' north and 1' east.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3/4" dia. aluminum rod 5' long/3-1/4" dia. aluminum cap (HDR Mon.) at the west terminus of an east-west fence. This corner location fits well with an old fence running south from this location and fits reasonably well with corner I-5 to the north. This corner has been used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 3/4" alum. rod 5' long/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. Cedar	N14°E	11.23 feet	Scr. NBT
6" dia. White Ash	S81°E	17.62 feet	Scr. NBT
6" dia. Cedar	S11°W	26.03 feet	Scr. NBT
9" dia. Maple	N75°W	20.75 feet	Scr. NBT
Carsonite Marker	S75°E	1.2 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 09, 1994
 Surveyor's Michigan License No. 26461

