

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T33N R27W	A07
	T R	
	T R	
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/12 19996
William Lenca
Chairman
412, BK 5
95 DEC 20 AM 9:36
REGISTERED LAND SURVEYOR
WILLIAM LENCA
26461
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER M-07 T33N-R28W

I, William Lenca, in a field survey on Jun. 27, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Hemlock, 12" - N82°W - 06 lks; Y. Pine, 14" - S51°W - 20 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1848: Original Survey (Sec. Subd) by John Mullett - B.T.'s - Y. Pine, 16" - N74°E - 32 lks; Hemlock, 20" - S51°E - 32 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: Certified Survey No. 233 recorded by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 18, T33N-R27W. The corner monument is not described and no witnesses are given.
- 1988: L.C.R.C. No. 814, Book 3, recorded by William Lenca, RLS No. 26461, states "Re-established corner in location indicated by Certified Survey No. 233." Set 5/8" x 24" Iron Rod/Ident. cap - TIES: Power Pole - S29°E - 34.75'; 16" W. Birch - S40°W - 51.64'; 6" S. Pine - S59°W - 86.18'; 9" Elm - N43°W - 132.70'

B. Description of corner evidence found and methods applied in restoring or reestablishing corner:

We found a 5/8 inch x 24" iron rod and 4 witnesses matching those described in L.C.R.C. No. 814 (see part "A") The measurements to corners 1/2 mile North and 1/2 mile West match closely with those recorded in Certified Survey No. 233. The corner falls in the centerline of county roads running North - East - West, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

12" dia. Cedar	S47°E	75.06 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	South	33.13 feet	
10" dia. White Pine	S59°W	86.18 feet	Scr. NET
9" dia. Elm	N43°W	132.63 feet	Scr. NBT
Survey Sign Post	South	34.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1996
Surveyor's Michigan License No. 26461

412