

SURVEY & REMONUMENTATION
APR 11 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 CE
 P.A. Of 1990 On 12/19 289 94
McDavid RL5
 ACTING Chairman

For corners in
MENOMINEE
 (County)

Located in: _____ Corner Code # _____

- 1. Public Land Survey T 33N R 27W _____ A-10
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property In Sec. S _____ T _____ R _____
 S _____ T _____ R _____

RECEIVED FOR RECORD
 94 DEC 12 AM 8:59
 PAGE # 107
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49858
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

William Lenca Oct. 04 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1847 - Original Survey (Township Exterior) by James H. Mullett - B.T.'s - Sugar Maple, 10" - S32°W - 25 lks; Birch, 6" - N53°W - 27 lks. All original evidence for this corner has been destroyed by County Road improvements.
 1901: Albert Haas, County Surveyor, made a survey of Section 25, T33N-R28W showing the location of this corner as it relates to other corners in this section. The survey states that a 4" Cedar Post was set equidistance between Section Corners. No. new B.T.'s are given.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 We measured the mile between the NW Corner and the SW Corner of Section 30, T33N-R27W, and found very old fences at 1/4 mile intervals that matched very closely with the 1901 Survey by Albert Haas. This led us to believe that the fences were built according to the 1901 Survey. We therefore placed the corner in line with an old fence West and in line with the centerline of a North-South County Road. We accepted this location as the best available evidence of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap - WITNESS MARKER	S39°W	44.90 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap - WITNESS MARKER	N86°W	24.03 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap - WITNESS MARKER	N35°W	36.10 feet
Survey Sign Post	N86°W	24.3 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1994
 Surveyor's Michigan License No. 26461

107