

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 12/16 199 96

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>MENOMINEE</u><br>(County)          | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>33N</u> R <u>27W</u> | <u>B07</u>    |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |

Chairman  
DEC 20, AM 9:36  
# 416, BR 5

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Jan 27, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  | •  |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Beech, 6" - S38°E - 07 lks; Beech, 6" - N62°E - 15 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: Certified Survey No. 233 recorded by George B. Wilson, RLS No. 17607, shows a subdivision of Section 18, T33N-R27W, and shows this corner as it relates to other corners in said section. No monument is shown or described - no new B.T.'s.
- 1988: L.C.R.C. No. 814, Book 3, recorded by William Lenca, RLS No. 26461, states "Re-established corner in location indicated by Certified Survey No. 233 - falls in c/l of E-W Co. Rd. & in line with old fence South. Set Railroad Spike - B.T.'s - Power Pole - S02°E - 33.31'; 5/8" dia. Iron - S50°W - 45.79'; 6" Poplar - N18°W - 33.96'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a railroad spike set in the centerline of an East - West County Road and in line with an old fence line running South. The position of this corner fits record measurements shown in Certified Survey No. 233. We also recovered the 3 witnesses as described in L.C.R.C. No. 814 (see part "A"). We accepted the location of the railroad spike as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

|   |       |            |                       |
|---|-------|------------|-----------------------|
| 8" dia. Poplar  | N18°W | 33.96 feet | Scr. NBT              |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S02°E | 33.50 feet | 1.0' E. of Power Pole |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | North | 31.77 feet |                       |
| Metal Survey Sign Post  | North | 32.5 feet  |                       |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 18, 1996



416