

SURVEY & REMONUMENTATION COMMISSION

APR 11 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1990 On 12/19, 19994

For corners in
MENOMINEE
(County)

Located in: _____ Corner Code # _____

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>33N</u> R <u>27W</u> | <u>B-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD
DEC 12 AM 8:59
Chairman
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11	●										
12	31	32	33	34	35	36					
13											

William Lenca

Sep 01, 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by John Mullett - B.T.'s - Black Ash, 4" - N41°W - 07 lks; Cedar, 4" - N27°E - 11 lks. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We established a proportional location for this corner, based upon the location of the SW and SE Corners of Section 30, T33N-R27W. We then ran the South Line of the Section, from the SE Corner to the proportioned position and searched an area of approximately 100' radius. We found no existing evidence of the corner location, so it was established at the proportional location as stated above. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2-1/2" dia. Alum. Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location: (Berntsen Driveable Monument)

6" dia. Tamarack	N65°E	28.66 feet	Scr. NBT
12" dia. Maple	S11°E	10.40 feet	Scr. NBT
8" dia. Tamarack	S62°W	27.67 feet	Scr. NBT
7" dia. Tamarack	N35°W	34.12 feet	Scr. NBT
Survey Sign Post	West	1.2 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.



Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 26, 1994