

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/9, 1999A

For corners in MENOMINEE
(County)

APR 11 1995

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
DEC 12 AM 8:59
Chairman
REGISTER OF DEEDS
BARBARA MORRISON
REMONUMENTATION 428659
112 BK 4

1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					

William Lenca

May 31

94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by John Mullett - B.T.'s - Cedar, 6" - N40°W - 15 lks; Cedar, 4" - S54°E - 11 lks. No original evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4" dia. aluminum rod 5' long/3-1/4" dia. aluminum cap set in place of the rotted remains of a pointed wood post lying next to the monument. Although there is no Land Corner Recordation Certificate for this corner, it is referred to in the private records of George B. Wilson, RLS No. 17607 with a distance shown from this corner to the section corner at C-9 as 2586.89'. Our measured distance for this line is 2586.62'. There are remnants of old fences running South and East from this location. We accepted the existing monument as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 3/4" dia. Alum. Rod 5' long/3-1/4" dia. Alum. cap stamped for corner location: (Berntsen Mon.)

5" dia. Tamarack	N33°E	20.40 feet	Scr. NBT
8" dia. Tamarack	S57°E	16.78 feet	Scr. NBT
7" dia. Tamarack	S17°W	6.55 feet	Scr. NBT
6" dia. Tamarack	N14°W	25.83 feet	Scr. NBT
Survey Sign Post	N15°E	0.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 26, 1994