

SURVEY & REMONUMENTATION

APR 1 1 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/9 19994

For corners in
MENOMINEE
(County)

COMMISSION

Located In:

Corner Code ##

- | | | | |
|------------------------------------|-----------------------------|-------|-------------------------|
| 1. Public Land Survey | T <u>33</u> N R <u>27</u> W | _____ | _____ <u>D-09</u> _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |

ACTING Chairman
MEL DAVIS RLS
 PAGE # 115 BK. 4
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49859
 RECEIVED FOR RECORD
 94 DEC 12 AM 8:59
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William Lenca

Oct. 06 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Hemlock, 18" - S33°E - 16 lks; Hemlock, 8" - N04°W - 16 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1981: Certified Survey No. 228 by William Lenca, RLS No. 26461, uses this corner for control for a partial subdivision of Section 20. The corner is described as a P.K. Nail. No. B.T.'s are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. Nail in the centerline of intersection of County Roads running North - South and East - West from this location. This corner has been used in several surveys over the past 13 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner, in Monument Box:

- | | | |
|---|-------|------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N33°E | 47.79 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S39°E | 45.21 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S51°W | 47.25 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N45°W | 49.11 feet |
| Survey Sign Post | N45°W | 49.3 feet |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1994

Surveyor's Michigan License No. 26461

115